

AD-A055 324

AIR FORCE AVIONICS LAB WRIGHT-PATTERSON AFB OHIO
TRANSIENT RESPONSE OF FILTERS. (U)

F/G 9/5

UNCLASSIFIED

DEC 77 J B TSUI, J E ADAIR, J E HAWKINS

AFAL-TR-77-249


A11

1 of 1

AD
A055 324



END
DATE
FILMED
8 -78
DDC



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

FOR FURTHER TRAN ~~74.11~~


(2)

AFAL-TR-77-249



TRANSIENT RESPONSE OF FILTERS

Passive ECM Branch
Electronic Warfare Division



December 1977

TECHNICAL REPORT AFAL-TR-77-249

Interim Report for the Period October 1975 to November 1977

Approved for public release; distribution unlimited

AD No. _____
DDC FILE COPY

AIR FORCE AVIONICS LABORATORY
AIR FORCE WRIGHT AERONAUTICAL LABORATORIES
Air Force Systems Command
Wright-Patterson Air Force Base, Ohio 45433

78 06 08 025

NOTICE

When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

This report has been reviewed by the Information Office (OI) and is releasable to the National Technical Information Service (NTIS). At NTIS, it will be available to the general public, including foreign nations.

This technical report has been reviewed and is approved for publication.

James B. Y. Tsui
J. B. Y. TSUI, PhD
Project Engineer

William F. Bahret
WILLIAM F. BAHRET
Chief, Passive ECM Branch
Electronic Warfare Division

FOR THE COMMANDER

Joseph H. Jacobs
JOSEPH H. JACOBS, Colonel, USAF
Chief, Electronic Warfare Division

"If your address has changed, if you wish to be removed from our mailing list, or if the addressee is no longer employed by your organization please notify AFAL/WRP, W-PAFB, OH 45433 to help us maintain a current mailing list".

Copies of this report should not be returned unless return is required by security considerations, contractual obligations, or notice on a specific document.

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER AFAL-TR-77-249	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER	
4. TITLE (and Subtitle) TRANSIENT RESPONSE OF FILTERS	5. TYPE OF REPORT & PERIOD COVERED Interim Report, for Oct 75 to Nov 77		
6. AUTHOR J.B.Y. Tsui, J.E. Adair, J.E. Hawkins, S.J. LaFleur	7. PERFORMING ORG. REPORT NUMBER		
8. PERFORMING ORGANIZATION NAME AND ADDRESS Air Force Avionics Laboratory (WRP) Wright-Patterson AFB, OH 45433	9. CONTRACT OR GRANT NUMBER(s)		
10. CONTROLLING OFFICE NAME AND ADDRESS Air Force Avionics Laboratory (WRP) Wright-Patterson AFB, OH 45433	11. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 62204F 7633 76331115		
12. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)	13. REPORT DATE December 1977		
	14. NUMBER OF PAGES 44		
	15. SECURITY CLASS. (of this report) Unclassified		
	16. DECLASSIFICATION/DOWNGRADING SCHEDULE		
17. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited			
18. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)			
19. SUPPLEMENTARY NOTES			
20. KEY WORDS (Continue on reverse side if necessary and identify by block number) Filter Response Transient Response Computer Modeling			
21. ABSTRACT (Continue on reverse side if necessary and identify by block number) One of the most important factors in designing receivers is to determine the transient response of the signal after it passes filters. It is time consuming and costly to measure the transient response experimentally. This report presents the theoretical analysis and a computer program to calculate filter transient response. Experimental data from both conventional and surface acoustic wave filters have also been presented to verify the validity of the program. The program can handle both Butterworth and Chebyshev filters and their combinations in cascade. The input signals can be a square, a composite, and a sine square wave. The computer program that calculates the transient response is also listed.			


DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

011 670

alt



FOREWORD

This report presents the theoretical analysis and a computer program to predict the transient response of band-pass filters with different input signals. This is an interim report in the continuing effort to evaluate channelized receivers.

This technical report was prepared by Dr. J.B.Y. Tsui of the Passive Electronic Countermeasures Branch, Electronic Warfare Division, and Dr. J.E. Adair of Microwave Technology Branch, Electronic Technology Division, The Air Force Avionics Laboratory, Wright-Patterson AFB, Ohio, under Project 7633, Task 1115. Mr. J.E. Hawkins of Systems Research Laboratory and Mrs. S.J. LaFleur of the Digital Programming Branch, ASD Computer Center, wrote the computer program for this report.

The authors wish to express their appreciation to K.R. Laker of the Air Force Cambridge Research Laboratory for the valuable discussions with him, and to C.P. Poirier of the ASD Computer Center and C. Gulley of Systems Research Laboratory for their help in the programming.

The work period for this effort extended from October 1975 to November 1977.

PRECEDING PAGE BLANK

ACCESSION for	
NDIS	Air Section <input checked="" type="checkbox"/>
DDC	B H Section <input type="checkbox"/>
UNANNOUNCED	<input type="checkbox"/>
JUSTIFICATION	
BY	
DISTRIBUTION/AVAILABILITY CODES	
U.	or SPECIAL
A	

78 06 08 025

TABLE OF CONTENTS

SECTION	PAGE
I INTRODUCTION	1
II MATHEMATICAL MODEL	2
1. Filters	2
2. Signals	4
III OUTPUT	5
1. Square Input Signal	5
2. Composite Signal	6
3. Sine Square Wave Signal	7
IV COMPUTER PROGRAM	8
V CALCULATED AND EXPERIMENTAL RESULTS FOR CONVENTIONAL FILTERS	8
VI APPROXIMATION OF SURFACE ACOUSTIC WAVE (SAW) FILTER	10
VII CONCLUSION	11
REFERENCES	11
APPENDIX: Computer Program Listing	33

PRECEDING PAGE BLANK

TABLE OF ILLUSTRATIONS

FIGURE	PAGE
1. Envelope of the composite input signal	12
2. Computer program functional flow diagram	13-15
3. Calculated output of a 3-pole Chebyshev filter with $f_0 = 300.8$ MHz $f = 17.8$ MHz, $RF = 0.25$ dB, the input signal is composite with $T_1 = 15$ ns, $T_2 = 190$ ns and $T_3 = 200$ ns	
a. Input frequency 301.1 MHz	16
b. Input frequency 309.8 MHz	16
c. Input frequency 317.0 MHz	17
4. Calculated output of a 5-pole Butterworth filter with $f_0 = 300.5$ MHz $f = 15.8$ MHz and square input signal of $T = 300$ ns	
a. Input frequency 300.5 MHz	17
b. Input frequency 291.4 MHz	18
c. Input frequency 292.6 MHz	18
5. Output of the 5-pole Butterworth filter with a sine squared input of $T = 20$ ns and $f = 300.5$ MHz	19
6. Insertion loss vs frequency of a 3-pole Chebyshev filter	20
7. Insertion loss vs frequency of a 5-pole Butterworth filter	20
8. Composite input signal with $T_1 = 15$ ns, $T_2 = 190$ ns and $T_3 = 200$ ns	21
9. Square signal $T = 300$ ns	21
10. Sine squared signal $T = 20$ ns	22
11. Measured output of the 3-pole Chebyshev filter	
a. Input frequency 301 MHz	22
b. Input frequency 309.8 MHz	23
c. Input frequency 310 MHz	23
12. Measured output of the 5-pole Butterworth filter	

TABLE OF ILLUSTRATIONS (CONTD)

FIGURE	PAGE
a. Input frequency 300.5 MHz	24
b. Input frequency 291.4 MHz	24
c. Input frequency 292.6 MHz	25
d. Input frequency 292.86 MHz	25
e. Input frequency 293.44 MHz	26
13. Measured output of the 5-pole Butterworth filter with a sine squared input signal	26
14. Insertion loss vs frequency of the SAW filter	27
15. Calculated output from the SAW filter	28
a. Input frequency 343.5 MHz	28
b. Input frequency 335.6 MHz	28
c. Input frequency 353.0 MHz	29
16. Measured output from the SAW filter	
a. Input frequency 343.5 MHz	30
b. Input frequency 335.6 MHz	30
c. Input frequency 353.0 MHz	31

SECTION I

INTRODUCTION

One of the most powerful methods of measuring frequency of several simultaneous signals, with limited frequency resolution required, is by using a bank of contiguous filters. If the incoming signal is continuous wave (CW), the frequency is relatively easy to determine, since the insertion loss characteristics of the filter are known. The relative outputs of two or more adjacent filters then identify frequency. If the incoming signal is pulse modulated, the output is a complex function of time, and requires more sophisticated detection schemes. To optimize the filter bank and the detection scheme, one has to know the output from different types of filters. It is time consuming and expensive to build the circuits and measure their performance (Reference 1).

The purpose of this report is to present an analytical procedure with computer calculations which determines the time response of the output signals, given the filter transfer characteristics. With this method, a large number of filters can be analyzed for the design of a channelized receiver without going through the construction and test phase. To document the validity of the analytical calculations, they are compared with measured performance of various filters.

The computer program is written to handle several kinds of band-pass filters, including Butterworth, Chebyshev, and a combination of two of these in cascade. The three kinds of pulsed carrier input signals used in the calculations are a square, a composite, and a sine square. The square

pulse is assumed to have infinitely sharp leading and trailing edges. The composite pulse has finite leading and trailing edges that can be selected independently. The sine square pulse is commonly used to approximate a short signal with slow rising and trailing edges.

SECTION II

MATHEMATICAL MODEL

In the calculations, the transfer functions of the filters are first predicted from the insertion loss versus frequency measurements; then the time domain impulse response of the transfer function is derived. The computer program then calculates the convolution of the input signals and the filter transfer function.

1. FILTERS

The filters are either specified or measured and their transfer function analytically fitted to the data, using a Butterworth or a Chebyshev model. The basic equation used to determine the number of poles is

$$V^2 = \frac{1}{1 + \left(\frac{\omega^2 - \omega_0^2}{\omega \Delta \omega} \right)^{2n}} \quad (1)$$

where V is the output voltage of the transfer filter function, ω is the angular velocity, and ω_0 is the center angular velocity of the filter. For a Butterworth filter, the poles are located as follows:

$$P_k = \Delta \omega \left[\cos \left(\frac{2k-1+n}{2n} \pi \right) + j \sin \left(\frac{2k-1+n}{2n} \pi \right) \right] \quad (2)$$

where

$$k = 1, 2, \dots, 2n,$$

$$\Delta \omega = 2\pi \times \text{bandwidth of the filter},$$

$$n = \text{number of poles of the filters.}$$

Only P_k with positive real parts are kept, and the poles corresponding to a band-pass filter are

$$S_k = \frac{P_k}{2} \pm j\omega \quad (3)$$

For the Chebyshev filters,

$$P_k = \Delta\omega (\tanh v \sin u_k + j\cos u_k) \quad (4)$$

$$u_k = \frac{\pi}{2n} (2k-1) \quad (5)$$

$$v = \frac{1}{n} \sinh^{-1} \left(\frac{1}{\epsilon} \right) \quad (6)$$

and

$$\epsilon = \sqrt{10^{R_f/10} - 1} \quad (7)$$

where $k = 1, 2, \dots, 2n$,

n = number of poles of the filters,

R_f = ripple factor in dB,

ω = $2\pi \times$ signal frequency, and

ω_0 = $2\pi \times$ filter center frequency.

Similarly, only P_k with positive real part are kept and the locations of the poles are calculated by equation (3). The transfer function of the filters is given as

$$\begin{aligned} H(s) &= \frac{(\Delta\omega)^n s^n}{(S+S_1)(S+S_2)\dots(S+S_{2n})} \\ &= \frac{A_1}{S+S_1} + \frac{A_2}{S+S_2} + \dots + \frac{A_{2n}}{S+S_{2n}} \end{aligned} \quad (8)$$

and the corresponding impulse response is

$$H(t) = A_1 e^{-S_1 t} + A_2 e^{-S_2 t} + \dots + A_{2n} e^{-S_{2n} t} \quad (9)$$

2. SIGNALS

The general shape of the input signal can be written as

$$R(t) = R_0(t) \cos \omega t = \frac{R_0(t)}{2} [e^{j\omega t} + e^{-j\omega t}] \quad (10)$$

where $\omega = 2\pi \times$ the carrier frequency of the signal and $R_0(t)$ = envelope of the input signal. For a square wave envelope input from $t = 0$ to $t = t_1$,

$$R_0(t) = U(t) - U(t-t_1) \quad (11)$$

where $U(t)$ is the step function. For a composite signal as shown in Figure 1,

$$R_0(t) = DtU(t) - D(t-t_1)U(t-t_1) - E(t-t_2)U(t-t_2) + E(t-t_3)U(t-t_3) \quad (12)$$

where $D = \frac{1}{t_1}$ and $E = \frac{1}{t_3-t_2}$.

For a sine square input,

$$R_0(t) = \sin^2 \frac{\pi t}{t_1} U(t) - \sin^2 \frac{\pi t}{t_1} U(t-t_1) \quad (13)$$

SECTION III

OUTPUT

The output from the filter is given by the convolution integral

$$Y(t) = \int_0^t R(\tau)H(t-\tau)d\tau \quad (14)$$

1. SQUARE INPUT SIGNAL

For the square input, Equation 14 becomes

$$Y(t) = U(t) \int_0^t R(\tau)H(t-\tau)d\tau - U(t-t_1) \int_{t_1}^t R(\tau)H(t-\tau)d\tau \quad (15)$$

For $t < t_1$

$$Y(t) = \sum_{k=1}^{2n} \left[Y_k(t) - Y_k(0) \right] \quad (16)$$

and for $t \geq t_1$

$$Y(t) = \sum_{k=1}^{2n} \left[Y_k(t_1) - Y_k(0) \right] \quad (17)$$

where

$$Y_k(\tau) = \frac{A_k e^{-S_k \tau}}{2} \left[\frac{e^{B_k \tau}}{B_k} + \frac{e^{C_k \tau}}{C_k} \right] \quad (18)$$

$$B_k = S_k + j\omega$$

and

$$C_k = S_k - j\omega$$

2. COMPOSITE SIGNAL

For the composite signal, the output for $t < t_1$ becomes

$$Y_{01}(t) = \sum_{k=1}^{2n} \left[DX_k(t) - DX_k(0) \right] \quad (19)$$

where

$$X_k(\tau) = \frac{A_k}{2} e^{-S_k \tau} \left[e^{B_k \tau} \left(\frac{\tau}{B_k} - \frac{1}{B_k^2} \right) + e^{C_k \tau} \left(\frac{\tau}{C_k} - \frac{1}{C_k^2} \right) \right] \quad (20)$$

for $t_1 \leq t < t_2$

$$Y(t) = \sum_{k=1}^{2n} \left[-DX_k(0) + DX_k(t_1) + Dt_1 Y_k(t) - Dt_1 Y_k(t_1) \right] \quad (21)$$

for $t_2 \leq t < t_3$

$$Y(t) = \sum_{k=1}^{2n} \left[-DX_k(0) + DX_k(t_1) + Dt_1 Y_k(t) - Dt_1 Y_k(t_1) - \right. \\ \left. EX_k(t) + EX_k(t_2) + Et_2 Y_k(t) - Et_2 Y_k(t_2) \right] \quad (22)$$

and for $t_3 \leq t$

$$Y(t) = \sum_{k=1}^{2n} \left[-DX_k(0) + DX_k(t_1) + Dt_1 Y_k(t) - Dt_1 Y_k(t_1) + \right. \\ \left. EX_k(t_2) + Et_2 Y_k(t) - Et_2 Y_k(t_2) - EX_k(t_3) - \right. \\ \left. Et_3 Y_k(t) + Et_3 Y_k(t_3) \right] \quad (23)$$

3. SINE SQUARE WAVE SIGNAL

For the sine square wave, the output for $t < t_1$ becomes

$$Y(t) = \sum_{k=1}^{2n} \left[Y_k(t) - Y_k(0) \right] \quad (24)$$

and for $t \leq t_1$

$$Y(t) = \sum_{k=1}^{2n} \left[Z_k(t_1) - Z_k(0) \right] \quad (25)$$

where

$$Z_k(\tau) = \frac{A_k e^{-S_k t}}{2} \left\{ \frac{e^{B_k \tau}}{\left(\frac{B_k t_1}{\pi} \right)^2 + 4} \left[\frac{B_k t_1}{\pi} \sin^2 \left(\frac{\pi \tau}{t_1} \right) - 2 \sin \left(\frac{\pi \tau}{t_1} \right) \cos \left(\frac{\pi \tau}{t_1} \right) + \right. \right. \\ \left. \left. \frac{2\pi}{B_k t_1} \right] + \frac{e^{C_k \tau}}{\left(\frac{C_k t_1}{\pi} \right)^2 + 4} \left[\frac{C_k t_1}{\pi} \sin^2 \left(\frac{\pi \tau}{t_1} \right) - \right. \right. \\ \left. \left. 2 \sin \left(\frac{\pi \tau}{t_1} \right) \cos \left(\frac{\pi \tau}{t_1} \right) + \frac{2\pi}{C_k t_1} \right] \right\} \quad (26)$$

A computer program which calculates Equations 16 through 26 and plots the results has been written and is shown in the appendix. The following section of this report discusses the computer program.

SECTION IV

COMPUTER PROGRAM

The flow diagram of the computer program shown in Figure 2 is presently set up to handle a maximum of $n = 12$ poles, but with minor changes it can handle a larger number of poles. Since only the envelope of the output is of interest, the program plots the envelope rather than the RF signal inside the pulse. The program will pick the minimum of $2\pi/\omega$ and $2\pi/\omega_0$ and use it as a standard time value. The first thirty local maximums are found using steps of $1/10\pi$ times the standard value. In order to minimize computation time, subsequent points are found by incrementing 0.8 of the standard value from the last maximum and then using steps of $1/10\pi$ times the standard value to find the next maximum. The estimated error in amplitude is

$$1 - \cos\left(\frac{1}{2} \cdot \frac{360}{10\pi}\right) = 0.005$$

or 0.5% with respect to the true maximum value.

SECTION V

CALCULATED AND EXPERIMENTAL RESULTS FOR CONVENTIONAL FILTERS

In order to cover all the possibilities, seven cases are calculated with the results as shown in Figure 3a through Figure 5. In these Figures, only the envelopes of the signals are plotted and their amplitudes are normalized according to the peak value of each individual output. In Figures 3a, 3b, and 3c, a 3-pole Chebyshev filter is used with a center frequency of 300.8 MHz, bandwidth of 17.8 MHz and a ripple factor of 0.25 dB. The input signals are all the composite waveform with $T_1 = 15$ ns, $T_2 = 190$ ns and $T_3 = 200$ ns. The center frequencies of the input used are

301 MHz, 309.8 MHz, and 317 MHz, respectively. In Figures 4a, 4b, and 4c, a 5-pole Butterworth filter is used having a center frequency of 300.5 MHz and bandwidth of 15.8 MHz. The input signals are all square wave with a pulse width T of 300 ns. The center frequencies of the input signals are 300.5 MHz, 291.4 MHz, and 292.6 MHz, respectively. In Figure 5, the same 5-pole Butterworth filter is used. The input signal is a sine square with $T_1 = 20$ ns and center frequency of 300.5 MHz. The amplitudes of all the outputs are normalized to unity and the times used are either 50 ns or 100 ns as shown in the figures. For a verification of the calculated results, experimental measurements are made for the same input waveforms. The RF pulse was generated by a RF switch and the output displayed on a Tectronix type 7904 oscilloscope.

Figures 6 and 7 show the insertion loss vs frequency of the three filters used for the analytical calculations above. The input signals are shown in Figures 8, 9, and 10. Figure 8 shows the composite signal, with $T_1 = 15$ ns, $T_2 = 190$ ns, and $T_3 = 200$ ns; Figure 9 shows the square wave signal of $T = 300$ ns; Figure 10 is the sine square signal of 20 ns. The outputs are shown in Figures 11a through 13. The frequencies are the same as specified in Figures 3a through 5. Figures 11a through 12a match the calculated results very well. However, the results of Figures 12b and 12c do not match Figures 4b and 4c as closely. By changing the frequency from 291.4 to 292.86 MHz and from 292.6 to 293.444 MHz as shown in Figures 12d and 12e, they match the calculated results better. Obviously, the frequency measurement, or the bandwidth of the filter measured, is off slightly. At the center of the filter the shape of the output signal is not very frequency dependent, but at the edge of the filter the

output depends very strongly on the frequency. In Figure 13, the measured result agrees with the calculated results rather well. However, the input signal, as shown in Figure 10, has some reflections in the time domain; and is not a true sine square signal. Thus, the output may deviate slightly from the ideal case.

SECTION VI

APPROXIMATION OF SURFACE ACOUSTIC WAVE (SAW) FILTER

A SAW filter with an insertion loss vs frequency as shown in Fig. 14 is used as the filter. This SAW filter was built by a cosine square time domain configuration on a pedestal (Ref. 3). This filter cannot be properly approximated by a single Butterworth or Chebyshev filter. However, it can be represented by two conventional filters in cascade. Both filters used in the analysis are Butterworth with the same center frequency of 343.5 MHz. One is a 7-pole filter with bandwidth of 9.5 MHz, the other is a single pole with bandwidth of 7.0 MHz. The input signal is a composite one with $T_1 = 25$ ns, $T_2 = 320$ ns, and $T_3 = 340$ ns. The center frequencies are 343.5 MHz, 335.6 MHz, and 353 MHz. The calculated and measured results are shown in Figures 15a, b, c, and 16a, b, c, respectively. In Figure 15a, c, and 16a, c, the results match fairly well; however, in Figure 15b and 16b the relative amplitudes between the two peaks are reversed in the calculated and measured results. It is suspected that the approximation is not close enough and may require a better combination of cascaded filters. For some SAW filters, the analytical model using Butterworth or Chebyshev filters must be modified by including the phase response in order to obtain the true time domain performance. A number of SAW filters are presently being measured to completely characterize their frequency domain performance and subsequently their time domain response.

SECTION VII

CONCLUSION

For the limited number of cases illustrated above, the computer program does generate a very accurate result for use in predicting the output of a filter. This program can be used to design receivers with filters, especially a channelized receiver which uses many filters. This program can also be extended to handle low-pass, high-pass, and band-rejection filters by using the appropriate filter transfer characteristics (Reference 2).

It also demonstrated that the transient response of some SAW filters can be approximated by this approach. The particular SAW filters that may be used in this approach are those displaying linear phase response in addition to providing Butterworth or Chebyshev amplitude response in the frequency domain.

REFERENCES

1. Hollis, R., "Double Detection Filter Techniques Test Report," Watkins-Johnson Co., Palo Alto, CA, 1973.
2. Chausi, M.S., "Principles and Design of Linear Active Circuits," Chapters 4, 15, McGraw-Hill, Inc., 1965.
3. Szabo, T.L., and Slobodnik, A.J., Jr., "Diffraction Compensation and Periodic Apodized Acoustic Surface Wave Filters," IEEE Trans. on Sonics and Ultrasonics U. SU-21, April 1974, pp 114-119.




Fig. 1 Envelope of the composite input signal




Fig. 2 Computer program functional flow diagram




Fig. 2 Computer program functional flow diagram (Con't)






Fig. 2 Computer program functional flow diagram (Con't)


Fig. 3 Calculated output of a 3-pole Chebyshev filter with $f_0 = 300.8$ MHz
 $f = 17.8$ MHz, $RF = 0.25$ dB, the input signal is composite with
 $T_1 = 15$ ns, $T_2 = 190$ ns and $T_3 = 200$ ns



3 a. Input frequency 301.1 MHz




3 b. Input frequency 309.8 MHz




3 c. Input frequency 317.0 MHz


Fig. 4 Calculated output of a 5-pole Butterworth filter with $f_0 = 300.5$ MHz
 $f = 15.8$ MHz and square input signal of $T = 300$ ns



4 a. Input frequency 300.5 MHz



4 b. Input frequency 291.4 MHz



4 c. Input frequency 292.6 MHz





Fig. 5 Output of the 5-pole Butterworth filter with a sine squared input
of $T = 20$ ns and $f = 300.5$ MHz



$f_0 = 300 \text{ MHz}$ 20 MHz/div 10 dB/div

Fig. 6 Insertion loss vs frequency of a 3-pole Chebyshev filter



$f_0 = 300 \text{ MHz}$ 20 MHz/div 10 dB/div

Fig. 7 Insertion loss vs frequency of a 5-pole Butterworth filter




Fig. 8 Composite input signal with $T_1 = 15$ ns, $T_2 = 190$ ns and $T_3 = 200$ ns




Fig. 9 Square signal $T = 300$ ns






Fig. 10 Sine squared signal $T = 20$ ns


Fig. 11 Measured output of the 3-pole Chebyshev filter



11 a. Input frequency 301 MHz




11 b. Input frequency 309.8 MHz




11 c. Input frequency 310 MHz


Fig. 12 Measured output of the 5-pole Butterworth filter




12 a. Input frequency 300.5 MHz




12 b. Input frequency 291.4 MHz



12 c. Input Frequency 292.6 MHz



12 d. Input frequency 292.86 MHz



12 e. Input frequency 293.44 MHz






Fig. 13 Measured output of the 5-pole Butterworth filter with a sine squared input signal




$f_0 = 343.5 \text{ MHz}$ 20 MHz/div 10 dB/div

Fig. 14 Insertion loss vs frequency of the SAW filter


Fig. 15 Calculated output from the SAW filter



15 a. Input frequency 343.5 MHz




15 b. Input frequency 335.6 MHz




15 c. Input frequency 353.0 MHz


Fig. 16 Measured output from the SAW filter



16 a. Input frequency 343.5 MHz



16 b. Input frequency 335.6 MHz



16 c. Input frequency 353.0 MHz

APPENDIX

COMPUTER PROGRAM LISTING

PROGRAM FILTER (INPUT,OUTPUT,TAPE4,TAPE5=INPUT,TAPE6=OUTPUT)

```

C-----
C THIS PROGRAM PROCESSES AN INPUT SIGNAL THROUGH AN N POLE FILTER.
C THE OUTPUT SIGNAL HAS A RELATIVE AMPLITUDE AS A FUNCTION OF TIME
C THE PROGRAM IS WRITTEN IN FORTRAN IV EXTENDED FOR A CDC6600.
C PLOTTING IS DONE ON AN OFFLINE CALCOMP PLOTTER.
C-----
      COMPLEX X1,X2,X3,X4,X5,X6,X7,X8,X88
      COMPLEX D4
      COMPLEX X61,X62,X63,X71,X72,X73
      COMPLEX A(48),B(48),C(48),OMEGA1,OMEGAJ,P(12),S(48),ST,ST2,TERM4,
1 Y(3),SS(24)
      DOUBLE DELT,T
      LOGICAL IY,IE,IFA,IEND
      LOGICAL IFP
      DIMENSION AH(2000),DATA(1024),TH(2000)
      DIMENSION FF(5),SF(5)
      COMMON/VARS/AH,AMPT,DELT,IVAR,L,M,T,TH,TMAX,XVAR,XVAR1,
1 YVAR,Y,DELT2,IFP,IFA
      NAMELIST/VALUE/KIS,SCF,T1,T2,T3,KF,NP,FCF,BW,RF,TMAX,CT,IVAR,XVAR,
1 YVAR,IY,IE,IFA,IEND,ICF,IFP
      NAMELIST/FIL2/KF,BW,NP,RF,FCF
      DATA IVAR,IEND,IY,IE,IFA,TMAX,PI,XVAR,YVAR/0,.T.,3*.F.,0.,
1 3.14159265358979,7.75,2.5/
      SINHI(X)=ALOG(X+SQRT(X**2+1.))
      ICF=1
C-----
C EACH FILTER SIMULATED MUST BE SPECIFIED BY A /VALUE/ NAMELIST.
C NAMELIST /FIL2/ CAN ONLY BE SPECIFIED FOR A COMPOSITE FILTER AND
C MUST IMMEDIATELY FOLLOW ITS RELATED FILTER'S /VALUE/ INPUT.
C THE INPUT PARAMETERS ARE INPUTED THROUGH NAMELIST/VALUE/ AND ARE AS
C FOLLOWS:
C   KIS = "KIND OF INPUT SIGNAL", MAY HAVE A VALUE FROM 1 THROUGH 3
C         IF 1, THEN THE SIGNAL IS A SQUARE WAVE
C         IF 2, THEN A RAMP TO PEAK, PEAK FOR SOME TIME, AND THEN A
C             NEGATIVE SLOPE TO 0 AMPLITUDE AT SOME LATER TIME
C         IF 3, THEN THE WAVE IS APPROXIMATED BY SINE SQUARED
C   SCF = "SIGNAL CENTER FREQUENCY" IN HERTZ
C   T1 = TIME DURATION OF SIGNAL FOR KIS = 1 OR 3 AND FOR KIS = 2
C         IT IS THE END OF THE RAMP (PEAK)
C   T2 = TIME DURATION OF PEAK SIGNAL + T1 FOR KIS = 2 ONLY
C   T3 = TIME DURATION OF NEGATIVE SLOPE + T1 + T2 FOR KIS = 2
C         ONLY
C   KF = "KIND OF FILTER", MAY HAVE A VALUE OF 1 OR 2
C         IF 1, THEN THE FILTER IS A BUTTERWORTH
C         IF 2, THEN THE FILTER IS A CHERYSHEV
C   NP = NUMBER OF POLES FOR THE FILTER (PRESENTLY LIMITED TO 12)
C   FCF = "FILTER CENTER FREQUENCY" IN HERTZ
C   BW = BANDWIDTH OF THE FILTER (BETWEEN -3 DB POINTS)
C   RF = RIPPLE FACTOR FOR CHERYSHEV FILTER
C   TMAX = MAXIMUM TIME DURATION OF OUTPUT SIGNAL (SEE NOTE BELOW)

```

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

```

C      CT      = MULTIPLIER WHICH IS THE NUMBER OF TIMES THE OUTPUT
C                SIGNAL EXCEEDS THE INPUT SIGNAL (SEE NOTE BELOW)
C      IVAR     = NUMBER OF ITERATIONS THAT ARE USED IN CALCULATING Y(I)
C      XVAP     = LENGTH OF X-AXIS OF PLOT (INCHES) INITIALLY; THIS VALUE
C                IS RECALCULATED IF THE AH(I) OR AL(I) ARRAYS ARE TOO
C                LARGE
C      YVAR     = HEIGHT OF Y-AXIS OF PLOT (INCHES); DOES NOT CHANGE
C      ICF=1    SINGLE FILTER
C      ICF=2    COMPOSITE FILTER
C      IV       = DECISION WHETHER TO WRITE OUT Y ARRAY
C                IF .TRUE. THEN THE ARRAY IS WRITTEN OUT
C                IF .FALSE. THEN THE ARRAY IS NOT WRITTEN OUT
C      IF       = DECISION WHETHER TO WRITE OUT ENVELOPS OF Y ARRAY
C                IF .TRUE. THEN THE ARRAY IS WRITTEN OUT
C                IF .FALSE. THEN THE ARRAY IS NOT WRITTEN OUT
C      IFP      = FREQUENCY PLOT ---PLOT IS DONE IF .TRUE.
C      IFA      = DECISION WHETHER TO WRITE OUT FREQUENCY ARRAY
C                IF .T. THEN ARRAY IS PRINTED
C                IF .F. THEN ARRAY IS NOT PRINTED
C      IEND     = DECISION WHETHER THERE IS ANOTHER SET OF DATA TO BE RUN
C                IF .TRUE. THEN ANOTHER SET IS RUN
C                IF .FALSE. THEN THE PROGRAM TERMINATES
C      NOTE:    IF TMAX IS SET AT 0, THEN TMAX = AMAX1(T1,T3)*CT, AND
C                IF IVAR IS SET AT 0, THEN IVAR = AMAX1(FCF,SCF)*2.*PI*
C                20.*TMAX+1.
C      FOR COMPOSITE FILTERS, PARAMETERS FOR THE SECOND FILTER ARE INPUT
C      THROUGH NAMEDLIST /FIL2/ AND ARE AS FOLLOWS:
C      KF      NP      FCF
C      BW      RF      SEE NAMEDLIST /VALUE/ FOR EXPLANATION OF
C      PARAMETERS.
C      FORMAT OF NAMEDLIST INPUT IS:
C      COL 1      BLANK
C      COL 2-7    'VALUE' OR 'FIL2'
C      COL 8      BLANK
C      COL 9-80   PARAMETER NAME FOLLOWED BY EQUAL SIGN FOLLOWED BY
C                  PARAMETER VALUE. SEPERATE PARAMETERS BY COMMAS AND
C                  END WITH A DOLLAR SIGN.
C      IF ONE CARD IS INSUFFICIENT - INPUT MAY BE CONTINUED ON OTHER
C      CARDS (START IN COL 2), BREAKING PARAMETER LIST AT ANY COMMA.

```

```

C-----
C      CALL PLOTS (DATA,1024,4)
C      CALL PLOT(0.,5.,-3)
C      WRITE (6,2000)
1     TSTART=SECONO(CP)
C      READ(5,VALUE)
C      FFF(1)=KF      FFF(2)=BW      FFF(3)=NP      FFF(4)=RF      FFF(5)=FCF
5     CONTINUE
C      IF(NP.GT.12) GO TO 700
C      WRITE (6,VALUE)
C      OMI=2.*PI*FCF
C      OMEGAI=CMPLX(0.,OMI)

```

```

OMJ=2.*PI*SCF
OMGAJ=CMPLX(0.,OMJ)
NP2=NP**2
TERM1=PW*2.*PI
M=0
GO TO (10,20),KF

```

C-----
C CALCULATION OF "P" VALUES FOR BUTTERWORTH FILTER
C-----

```

10 DO 11 I=1,NP
   TERM2=FLOAT(2*I-1+NP)/FLOAT(NP2)*PI
   TPR=-TERM1*COS(TERM2)
   TPI=TERM1*SIN(TERM2)
   P(I)=CMPLX(TPR,TPI)
11 WRITE (6,3000) I,P(I)
   GO TO 30

```

C-----
C CALCULATION OF "Q" VALUES FOR CHEBYSHEV FILTER
C-----

```

20 EI=1./SQRT(10.**((PF/10.)-1.))
   V=1./FLOAT(NP)*SINH(EI)
   DO 21 I=1,NP
   U=PI/FLOAT(NP2)*FLOAT(2*I-1)
   TPR=TANH(V)*SIN(U)*TERM1
   TPI=COS(U)*TERM1
   P(I)=CMPLX(TPR,TPI)
21 WRITE (6,3000) I,P(I)

```

C-----
C CALCULATION OF "S" VALUES
C-----

```

30 J=0
   DO 31 I=2,NP2,2
   J=J+1
   IM1=I-1
   S(T-1)=P(J)/2.+OMGAJ
   S(I)=P(J)/2.-OMGAJ
31 WRITE (6,3001) IM1,S(I-1),I,S(I)
   GO TO (35,400,450)ICF

```

C-----
C CALCULATION OF "A" VALUES
C-----

```

35 CONTINUE
   DO 32 I=1,NP2
   ST=-S(I)
   TERM4=CMPLX(1.,0.)
   DO 33 J=1,NP2
   IF (I.EQ.J) GO TO 33
   TERM4=TERM4*(ST+S(J))
33 CONTINUE
   ST2=ST**NP

```


C WRITE (6,2001) "ST2=",ST2,"TERM4=",TERM4

2001 FORMAT(1X,A4,2E19.10,5X,A6,2E19.10)

A(I)=ST2/TERM4

32 WRITE (6,3002) I,A(I)

C CALCULATION OF "IVAR" AND "TMAX" IF NECESSARY

IF (FLOAT(IVAR).GT.0..AND.TMAX.GT.0.) GO TO 40

IF (TMAX.GT.0.) GO TO 41

TMAX=AMAX1(T1,T3)*CT

IF (IVAR.GT.0.) GO TO 40

41 IVAR=AMAX1(OMI,OMJ)*5.*TMAX+1.

40 DELT=TMAX/FLOAT(IVAR-1)

WRITE (6,2002) IVAR,DELT

DELT2=.9*AMIN1(1./FCF,1./SCF)

T=DELT

Y(1)=CMPLX(0.,0.)

GO TO (100,200,300),KIS

C COMPOSITE FILTERS

400 DO 410 I=1,NP2

410 SS(I)=S(I)

ICF=ICF+1

READ(5,FIL2)

SF(1)=KF \$SF(2)=RW \$SF(3)=NP \$SF(4)=RF \$SF(5)=FCF

GO TO 5

450 J=NP2+2*FF(3)

IF(J.GT.48)GO TO 700

K=NP2+1 \$NSP=0

DO 460 I=K,J

NSP=NSP+1

460 S(I)=SS(NSP)

IF(FF(2).LT.RW)RW=FF(2)

NP=J/2

NP2=J

WRITE(6,3001)(J,S(J),J=1,NP2)

GO TO 35

C CALCULATION OF OUTPUT SIGNAL FOR SQUARE WAVE INPUT SIGNAL

100 DO 101 I=2,IVAR

L=MIN0(3,I)

Y(L)=CMPLX(0.,0.)

TT=SNGL(T)

DO 102 I=1,NP2

X1=CEXP(-S(J)*TT)

C PRINT *, "X1=",X1," T=",TT

X2=S(J)+OMEGAJ

X3=S(J)-OMEGAJ

IF(TT.GT.T1)GO TO 103


```

      X4=OMEGAJ*TT
C      PRINT *, " X4=", X4
      Y(L)=Y(L)+A(J)/2.*((CEXP(X4)-X1)/X2+(CEXP(-X4)-X1)/X3)
      GO TO 102
103    Y(L)=Y(L)+A(J)/2.*X1*((CEXP(X2*TT)-1.)/X2+(CEXP(X3*TT)-1.)/X3)
      102 CONTINUE
      IF(.NOT.IV) GO TO 105
      IM1=I-1
      IF (I.EQ.2) WRITE (6,2003) IM1,Y(IM1)
      WRITE (6,2015) I,Y(L)
C-----
C  CALCULATION OF ENEVELOP
C-----
105    CALL ARRAY
      IF(T.GT.TMAX)GO TO 500
      101 T=T+DELT
      GO TO 500
C-----
C  CALCULATION OF OUTPUT SIGNAL FOR COMPOSITE WAVE INPUT SIGNAL
C-----
      200 D=1./T1
      E=1./(T3-T2)
      DO 211 I=1,NP2
      B(I)=S(I)+OMEGAJ
      C(I)=S(I)-OMEGAJ
      211 WRITE (6,3004) I,B(I),I,C(I)
      WRITE (6,3003) D,E
      DO 201 I=2,IVAR
      TT=SNGL(T)
      L=MIN0(3,I)
      Y(L)=CMPLX(0.,0.)
      DO 202 J=1,NP2
      X1=CEXP(-S(J)*TT)
      X2=CEXP(OMEGAJ*TT)
      X3=CEXP(-OMEGAJ*TT)
      X5=1./C(J)**2
      X4=1./B(J)**2
      IF(TT.LE.T1)GO TO 203
      X6=CEXP(B(J)*TT)
      X7=CEXP(C(J)*TT)
      X61=CEXP(B(J)*T1)
      X71=CEXP(C(J)*T1)
      IF(TT.LE.T2)GO TO 204
      X62=CEXP(B(J)*T2)
      X72=CEXP(C(J)*T2)
      IF(TT.LE.T3)GO TO 205
      X63=CEXP(B(J)*T3)
      X73=CEXP(C(J)*T3)
      GO TO 205
      203 Y(L)=Y(L)+D*A(J)/2.*((X1-X2)*X4+X2*TT/B(J)+(X1-X3)*X5+X3*TT/C(J))
      GO TO 212

```

```

204  Y(L)=Y(L)+D*A(J)/2.*X1*((X61*(T1/R(J)-X4)+X71*(T1/C(J)-X5))+
1  X4+X5+T1*((X6-X61)/B(J)+(X7-X71)/C(J)))
    GO TO 202
205  Y(L)=Y(L)+A(J)/2.*X1*(D*(X4+X5+X61*(T1/R(J)-X4)+X71*(T1/C(J)-X5)
1  +T1*((X6-X61)/B(J)+(X7-X71)/C(J)))-E*(X6*(T/B(J)-X4)+X7*(T/
2  C(J)-X5)-X62*(T2/R(J)-X4)-X72*(T2/C(J)-X5)-T2*((X5-X62)/
3  B(J)+(X7-X72)/C(J))))
    GO TO 202
206  Y(L)=Y(L)+A(J)/2.*X1*(D*(X4+X5+X61*(T1/R(J)-X4)+X71*(T1/C(J)-X5)
1  +T1*((X6-X61)/B(J)+(X7-X71)/C(J)))+E*(X62*(T2/B(J)-X4)+X72*
2  (T2/C(J)-X5)+T2*((X6-X62)/B(J)+(X7-X72)/C(J))-X63*(T3/B(J)-
3  X4)-X73*(T3/C(J)-X5)-T3*((X6-X63)/B(J)+(X7-X73)/C(J)))
202  CONTINUE
    IF(.NOT.IV) GO TO 215
    IM1=I-1
    IF (I.F0.2) WRITE (6,2003) IM1,Y(I+1)
    WRITE (6,2015) I,Y(L)

```

C-----
C CALCULATION OF ENVELOPE
C-----

```

215  CALL ARRAY
    IF(T.GT.TMAX)GO TO 500
201  T=T+DELT
    GO TO 500

```

C-----
C CALCULATION OF OUTPUT SIGNAL FOR SINE SQUARED WAVE INPUT SIGNAL
C-----

```

300  DO 305 I=1,NP2
    R(I)=S(I)+OMEGAJ
    C(I)=S(I)-OMEGAJ
305  WRITE (6,2004) I,B(I),I,C(I)
    DO 301 I=2,IVAR
    L=MIN0(3,I)
    Y(L)=CMPLX(0.,0.)
    TT=SNGL(T)
    DO 302 J=1,NP2
    IF(TT.GE.T1)GO TO 303
    Y1=CEXP(-OMEGAJ*TT)
    X2=CEXP(OMEGAJ*TT)
    R1=T1/PI
    X3=R(J)*R1
    X4=C(J)*R1
    D1=PI*TT/T1
    D2=SIN(D1)
    D3=COS(D1)
    D4=X3*D2*D2-2.*D2*D3
    X8=CEXP(-S(J)*TT)
    X5=2.*PI/(B(J)*T1)
    X6=X2/(2.*X3*Y3+X8.)*(D4+X5)
    D4=X4*D2*D2-2.*D2*D3
    X7=X1/(2.*X4*X4+X8.)*(D4+2.*PI/(C(J)*T1))

```

```

X88=X8*PI**3      X9=T1**3
R2=4.*PI*PI*T1
Y(L)=Y(L)+A(J)*(X6+X7-X88/(B(J)**3*X9+R2*B(J))-X88/(X9*C(J)**3
1  +R2*C(J)))
GO TO 302
303  X1=A(J)*CEXP(-S(J)*T1)*PI
      X2=P(J)*T1
      X3=P(J)**3
      R1=T1**3
      R2=PI*PI
      R3=R1/R2
      X4=CEXP(X2)/(X3*R3+4.*X2)
      X5=R2/(X3*R1+4.*R2*X2)
      X2=C(J)*T1
      X3=C(J)**3
      X6=CEXP(X2)/(X3*R3+4.*X2)
      X7=P2/(X3*R1+4.*R2*X2)
      Y(L)=Y(L)+X1*(X4+X6-X5-X7)
302  CONTINUE
      IF(.NOT.IY) GO TO 306
      IM1=I-1
      IF (I.EQ.2) WRITE (6,2003) IM1,Y(IM1)
      WRITE (6,2015) I,Y(L)
C-----
C  CALCULATION OF ENVELOPE
C-----
306  CALL ARRAY
      IF(T.GT.TMAX)GO TO 500
301  T=T+DELT
500  IF(.NOT.IE) GO TO 600
      WRITE(6,2004)
      DO 503 I=1,M
503  WRITE (6,2005) I,AH(I),I,TH(I)
C-----
C  DETERMINATION OF ABSOLUTE MAXIMUM AMPLITUDE OF ARRAY
C-----
600  CALL MAXAMP
      WRITE (6,2008) AMPT
C-----
C  CALCULATION OF ARRAY COORDINATES FOR CALCOMP PLOTTER
C-----
      CALL COORD
C-----
C  OFFLINE CALCOMP PLOTTING ROUTINE
C-----
602  CALL GRAPH(KIS,SCF,T1,T2,T3,ICF,FF,SF)
      WRITE (6,VALUE)
      IF(IEND) GO TO 4
2  WRITE (6,2013)
      CALL PLOTE(NAME)
      WRITE (6,2014) NAME

```


THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

```

TSTOP=SECOND(OP)
DELTAT=TSTOP-TSTART
WRITE (6,4000) TSTART,TSTOP,DELTAT
STOP
4 IVAR=0
TMAX=0.
ICF=1
TSTOP=SECOND(OP)
DELTAT=TSTOP-TSTART
WRITE (6,4000) TSTART,TSTOP,DELTAT
GO TO 1
700 WRITE(6,4001)
STOP
4001 FORMAT(*THE NUMBER OF POLES OF THE FILTER EXCEEDS THE ALLOCATED
10DIMENSION*/)
2000 FORMAT (1H1,*THE FOLLOWING PORTION OF THIS PRINT OUT IS THE OUTPUT
A SECTION*)
2002 FORMAT (1H0///// IVAR = *,I7,10X,* DELT = *,1P017.10/)
2003 FORMAT (1H1,*THE FOLLOWING OUTPUT IS THE COMPLEX Y FOR EACH DELTA
ATIME INCREMENT///// Y(*,I6,*) = *,1P2E19.10)
2004 FORMAT (1H1,*THE FOLLOWING OUTPUT IS THE ARRAY OF LOCAL MAXIMUMS (
ASUBSET OF COMPLEX VARIABLES) AND TIME*/)
2005 FORMAT (1H ,*AH(*,I4,*) = *,1PE19.10,* TH(*,I4,*) = *,E19.10)
2006 FORMAT (1H1,*THE FOLLOWING OUTPUT IS THE ARRAY OF LOCAL MINIMUMS (
ASUBSET OF COMPLEX VARIABLES) AND TIME*/)
2007 FORMAT (1H ,*AL(*,I4,*) = *,1PE19.10,* TL(*,I4,*) = *,E19.10)
2008 FORMAT (1H0///// ABSOLUTE MAXIMUM AMPLITUDE IS EQUAL TO *,1PE17.10)
2013 FORMAT (1H0///// THIS STATEMENT TERMINATES THIS RUN*)
2014 FORMAT (1H0///// THE NUMBER OF BLOCKS ON THE PLOTTING TAPE IS *,I5)
2015 FORMAT (1H ,*Y(*,I6,*) = *,1P2E19.10)
3000 FORMAT (1H0,*P(*,I2,*) = *,1P2E19.10)
3001 FORMAT (1H0,*S(*,I2,*) = *,1P2E19.10,* S(*,I2,*) = *,2E19.10)
3002 FORMAT (1H0,*A(*,I2,*) = *,1P2E19.10)
3003 FORMAT (1H0,*D = *,1PE19.10,* E = *,E19.10)
3004 FORMAT (1H0,*B(*,I2,*) = *,1P2E19.10,* C(*,I2,*) = *,2E19.10)
4000 FORMAT (1H0,*THIS RUN STARTED AT TIME *,F7.3,* AND ENDED AT *,F7.3
A,* TAKING *,F7.3,* SECONDS TO EXECUTE*///)
END
SUBROUTINE ARRAY
C-----
C ROUTINE TO LIMIT OUTPUT OF ENVELOP ARRAYS
C-----
COMPLEX Y(3)
DOUBLE DELT,T
DIMENSION AH(2000),TH(2000)
COMMON/VARS/AH,AMPT,DELT,IVAR,L,M,T,TH,TMAX,XVAR,XVAR1,
AYVAR,Y,DELT2,IFP,IFA
IF (L.EQ.2) GO TO 2
IF (L.NE.3) GO TO 7
YMAX=AMAX1(REAL(Y(L-2)),REAL(Y(L-1)),REAL(Y(L)))

```



```

      IF (YMAX.EQ.REAL(Y(L-1))) GO TO 3
      GO TO 5
3     IF(Y(L-2).EQ.CMPLX(0.,0.))GO TO 5
      M=M+1
      IF(M.GT.2000) GO TO 6
      TH(M)=SNGL(T)
      AH(M)=REAL(Y(L-1))
      IF(M.LE.30)GO TO 5
      Y(L-1)=Y(L)=CMPLX(0.,0.)
      T=T+DELT2-DELT
C     WRITE(6,3000)Y(L-1),TH(M)
      GO TO 5
2     M=1
      TH(M)=SNGL(T-DELT)
      AH(M)=REAL(Y(L-1))
      RETURN
5     Y(L-2)=Y(L-1)
      Y(L-1)=Y(L)
      RETURN
6     WRITE (6,2000)
      STOP
7     WRITE (6,2001)
      STOP
2000 FORMAT (1H1,*THE PLOTTING ARRAY EXCEEDS THE ALLOCATED DIMENSION OF
A 2000*)
2001 FORMAT (1H1,*ERROR IN THE CALCULATION OF L COUNTER*)
3000 FORMAT(5X,*Y=*,1P7E19.10,*J MAX T=*,E19.10)
3001 FORMAT(5X,*Y=*,1P7E19.10,*J MIN T=*,E19.10)
      END
      SUBROUTINE MAXAMP
C-----
C ROUTINE TO CALCULATE ABSOLUTE MAX SIGNAL AMPLITUDE
C-----
      COMPLEX Y(3)
      DOUBLE DELT,T
      DIMENSION AH(2000),TH(2000)
      COMMON/VARS/AH,AMPT,DELT,IVAR,L,M,T,TH,TMAX,XVAR,XVAR1,
      AYVAR,Y,DELT2,IFD,IFA
      AMPT=AH(1)
      DO 1 I=2,M
1     AMPT=AMAX1(AMPT,AH(I))
      RETURN
      END
      SUBROUTINE COORD
C-----
C ROUTINE TO CALCULATE PLOTTER COORDINATES IN INCHES
C-----
      COMPLEX Y(3)
      DOUBLE DELT,T
      DIMENSION AH(2000),TH(2000)
      COMMON/VARS/AH,AMPT,DELT,IVAR,L,M,T,TH,TMAX,XVAR,XVAR1,
      AYVAR,Y,DELT2,IFD,IFA

```

```

      YVAR1=XVAR
2    IF(FLOAT(M-1).LE.XVAR1*100.)GO TO 1
      XVAR1=XVAR1*1.1
      GO TO 2
1    WRITE (6,2000) XVAR1,YVAR
2000 FORMAT (1H0////* LENGTH OF THE X-AXIS IS *,F5.3,* INCHES, AND THE
      HEIGHT OF THE Y-AXIS IS *,F6.3,* INCHES*)
      END
      SUBROUTINE GRAPH(XIS,SCF,T1,T2,T3,ICF,FF,SF)
-----
C ROUTINE TO PLOT ARRAYS
C -----
      COMPLEX Y(3)
      DOUBLE DELT,T
      LOGICAL IFP,IFA
      DIMENSION FF(5),SF(5)
      DIMENSION AH(2000),TH(2000)
      DIMENSION IT(8),ITL(5)
      COMMON/VARS/AH,AMPT,DELT,IVAR,L,M,T,TH,TMAX,XVAR,XVAR1,
1YVAR,Y,DELT2,IFP,IFA
      DATA(IT(I),I=1,8)/6HSQUARE,9HCOMPOSITE,10HSINE SQUAR,2HED,
1 10HPUTTERWORT,14H,9HCHEBYSHEV,5HPOLES/
      DATA(ITL(I),I=1,5)/6,9,12,11,3/
      AH(M+1)=TH(M+1)=0.
      TH(M+2)=TMAX/XVAR1
      AH(M+2)=AMPT/2.5
      CALL AXIS(0.,-YVAR,15HTIME (MSECONDS),-15,XVAR1,0.,TH(M+1),TH(M+2)
1)
      TYV=YVAR*2.
      CALL AXIS(0.,-YVAR,18HRELATIVE AMPLITUDE,18,TYV,90.,-1.,.4)
      CALL PLOT(0.,0.,3)
      CALL PLOT(XVAR1,0.,2)
      CALL PLOT(0.,0.,3)
      CALL LINE(TH,AH,M,1,0.,4)
      DO 2 I=1,M
2    AH(I)=-AH(I)
      CALL LINE(TH,AH,M,1,0.,4)
      XPLUS=XVAR1+3.25
C INPUT SIGNAL
      H=.14
      CALL SYMBOL(0.5,-3.7,H,13HINPUT SIGNAL(,0.,13)
      CALL SYMBOL(2.37,-3.7,H,IT(KIS),0.,ITL(KIS))
      CALL SYMBOL(2.37,-3.9,H,3HF=,0.,3)
      CALL SYMBOL(2.44,-3.9,.07,1HC,0.,1)
      FC=SCF
      CALL NUMBER(2.77,-3.9,H,FC,0.,2)
      CALL SYMBOL(3.57,-3.9,H,3HMH7,0.,3)
      CALL SYMBOL(2.37,-4.1,H,3HT1=,0.,3)
      XT=T1
      CALL NUMBER(2.77,-4.1,H,XT,0.,3)
      CALL SYMBOL(3.57,-4.1,H,4HMH7,0.,4)

```

```

IF(T2.EQ.0.)GO TO 5
CALL SYMBOL(2.37,-4.3,H,3HT2=,0.,3)
YT=T2
CALL NUMBER(2.77,-4.3,H,YT,0.,3)
CALL SYMBOL(3.57,-4.3,H,4HMSFC,0.,4)
IF(T3.EQ.0.)GO TO 5
CALL SYMBOL(2.37,-4.5,H,3HT3=,0.,3)
YT=T3
CALL NUMBER(2.77,-4.5,H,YT,0.,3)
CALL SYMBOL(3.57,-4.5,H,4HMSFC,0.,4)
C FILTER
5 CALL SYMBOL(4.5,-3.7,H,7HFILTER:,0.,7)
KF=FF(1)
CALL SYMBOL(5.6,-3.7,H,IT(2*KF+3),0.,ITL(KF+3))
CALL SYMBOL(5.6,-3.9,H,3HF=,0.,3)
CALL SYMBOL(5.73,-3.9,.07,1HC,0.,1)
CALL NUMBER(5.1,-3.9,H,FF(5),0.,2)
CALL SYMBOL(7.1,-3.9,H,3HMHZ,0.,3)
CALL NUMBER(5.6,-4.1,H,FF(3),0.,-1)
CALL SYMBOL(5.9,-4.1,H,IT(8),0.,5)
CALL SYMBOL(5.6,-4.3,H,3HRW=,0.,3)
CALL NUMBER(5.1,-4.3,H,FF(2),0.,2)
CALL SYMBOL(7.1,-4.3,H,3HMHZ,0.,3)
IF(FF(4).EQ.0.)GO TO 8
CALL SYMBOL(5.6,-4.5,H,5HRF=,0.,5)
CALL NUMBER(6.2,-4.5,H,FF(4),0.,2)
8 IF(ICF.EQ.1)GO TO 10
X=7.5      *XY=-3.7
CALL SYMBOL(X,XY,H,7HFILTER:,0.,7)
Y=Y+1.1      *KF=SF(1)
CALL SYMBOL(X,XY,H,IT(2*KF+3),0.,ITL(KF+3))
XY=XY-.2
CALL SYMBOL(X,XY,H,3HF=,0.,3)
CALL SYMBOL(X+.13,XY,.07,1HC,0.,1)
FC=SF(5)
CALL NUMBER(X+.5,XY,H,FC,0.,2)
CALL SYMBOL(X+1.5,XY,H,3HMHZ,0.,3)
XY=XY-.2
CALL NUMBER(X,XY,H,SF(3),0.,-1)
CALL SYMBOL(X+.3,XY,H,IT(8),0.,5)
XY=XY-.2
CALL SYMBOL(X,XY,H,3HRW=,0.,3)
FC=SF(2)
CALL NUMBER(X+.5,XY,H,FC,0.,2)
CALL SYMBOL(X+1.5,XY,H,3HMHZ,0.,3)
IF(SF(4).EQ.0.)GO TO 10
XY=XY-.2
CALL SYMBOL(X,XY,H,3HRF=,0.,3)
CALL NUMBER(X+.5,XY,H,SF(4),0.,2)
10 IF(.NOT.IFPI)GO TO 40
IM=M-1

```


THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

```

DO 20 I=1,IM
  AH(I)=1./((TH(I+1)-TH(I))-SCF
  AH(M)=AH(M+1)=AH(10)
  IM=M-1
  DO 30 I=10,IM
    AH(M)=AMIN1(AH(M),AH(I))
  30  AH(M+1)=AMAX1(AH(M+1),AH(I))
    AH(M+1)=(AH(M+1)-AH(M))/2.5
    PRINT *, "  AH(M)=", AH(M), "      AH(M+1)=", AH(M+1)
    TH(M)=0.
    TH(M+1)=TMAX/XVAR1
    CALL AXIS(XVAR1,0.,15HFREQUENCY IN HZ,-15,YVAR,90.,AH(M),AH(M+1))
    CALL DASHLN(TH(10),AH(10),IM-9,1)
    IF(.NOT.IFA)GO TO 40
    WRITE(6,50) (I,AH(I),I,TH(I),I=10,IM)
  50  FORMAT(*1 THE FOLLOWING OUTPUT IS COMPUTED SIGNAL FREQUENCY*
1 (*  FP(*,I4,*) = *,E19.10,*      TH(*,I4,*) = *,E19.10))
  40  CALL PLOT(XPLUS,0.,-3)
    RETURN
  END
**

```